

2.4.3	Indoor Fire Hose Cabinet, Surfaced Type, Complete with 40mm Ø Angle Hose Valve, 40mm Ø Hose Nozzle, 40mm Ø x 30m Fire Hose Double Jacket and, and Hose Rack	16	set						
2.5. Inspector's Test Connection				1	lot				
2.5.1	Sight Glass, 25mm Ø	5	pc						
2.5.2	Gate Valve 25mm Ø, UL/FM	5	pc						
2.6. Pipes and Fittings				1	lot				
2.6.1	100mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	38	pc						
2.6.2	80mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	125	pc						
2.6.3	65mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	29	pc						
2.6.4	50mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	15	pc						
2.6.5	40mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	6	pc						
2.6.6	32mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	288	pc						
2.6.7	25mm Ø, Black Steel Pipe Sch.40 Seamless Plain Ends ASTM A53 Gr. B 6m	94	pc						
2.6.8	Fittings, Sch.40, Black Steel (Elbow Standard, Tee Straight, Tee Reducer, Concentric Reducer, Eccentric Reducer, Grooved Fittings, Slip On Flange, Blind Flange, B.I. End Cap and Etc.)	1	lot						
2.6.9	Pipe Hangers, Supports and Sleeves	1	lot						
2.6.10	Epoxy Enamel Paint for Steel Pipes (including surface preparation, primer and 2 top coats and primer)	1	lot						
2.7. Sprinklers Heads, FHCs, and Accessories				1	lot				
2.7.1	K = 5.6, Quick Response, 155°F, 1/2" NPT, Pendent Type w/ escutcheon plate	12	pc						
2.7.2	Indoor Fire Hose Cabinet, Surfaced Type, Complete with 40mm Ø Angle Hose Valve, 40mm Ø Hose Nozzle, 40mm Ø x 30m Fire Hose Double Jacket and, and Hose Rack	20	set						
3 Structural Works									
3.1 Concrete and Steel Works				1	lot				
3.1.1	Excavation	1167.94	m³						
3.1.2	Concrete 3000 psi	70.41	m³						
3.1.3	Reinforcement								
3.1.3.1	16mm Ø x 6m DSB Grade 40	3227.47	kg						
3.1.3.2	12mm Ø x 6m DSB Grade 40	1083.51	kg						
3.1.3.3	10mm Ø x 6m DSB Grade 40	335.28	kg						
3.1.4	#16 GI Tie Wire	78.00	kg						
3.1.5	20 mm Ø Stainless Steel Bar Ladder Rung	9	pc						
3.2 Roof Framing				1	lot				
3.2.1	2" x 4" x 1.5 mm thk. G.I. Tubulars	5	pc						
3.2.2	2" x 4" x 1.5 mm thk. G.I. C- Purlins	10	pc						
3.2.3	2" x 10" x 1.5 mm thk. G.I. C- Purlins	4	pc						
3.2.3	1 1/2" x 1 1/2" x 3.5 mm thk. Anglebar	1	pc						
3.2.3	10mm Ø Round Bar	2	pc						
3.2.4	Epoxy Primer Paint for Steel Framing	1	lot						
3.2.5	Welding Rods	1	lot						

4 Architectural Works						
4.1 Masonry and Plastering Works						
				1	lot	
4.1.	4" CHB Wall (including mortar and 10 mm steel reinforcement every three CHB layer and 0.60 m horizontal spacing)	46.92	m ²			
4.2.	Cement Plastering of Interior and Exterior Walls, Column, Beams, etc.	89.42	m ²			
4.2 Roofing Materials						
				1	lot	
4.2.1	0.50 mm thk. Pre-painted Rib Type Roofing	34.00	m			
4.2.2	0.50 mm thk. Pre-painted Roof Flashing	9.00	m			
4.2.3	0.50 mm thk. Pre-painted Roof Gutter	3.00	m			
4.2.4	10 mm thk. Aluminum Fim Laminated Foam Two Sided w/ 12.5 mm welded wire #21	34.00	m ²			
4.2.5	Tekscrew,Blind Rivets,Sealant, etc.	1	lot			
4.3 Floor Finishing Works						
				1	lot	
4.3.1	Smooth Cement Floor Finish	14.61	m ²			
4.4 Ceiling Works						
				1	lot	
4.4.1	6" x 0.50 mm Pre- Painted Metal Spandrel including air ventilation holes, mouldings and framing system	20.00	m ²			
4.5 Painting and Water Proofing Works						
				1	lot	
4.5.1	Semi-Gloss Latex Paint Finish on Exterior and Interior Wall, Beams, Columns, Ledges, etc. (surface preparation, primer and 2 top coats)	89.42	m ²			
4.5.2	Waterproofing of inside perimeter wall and floor (surface preparation, application of 5 coats of cementitious waterproofing)	75.24	m ²			
4.6 Doors						
				1	lot	
4.6.1	D1 - Double Swing Steel Louver Door with Metal Door Jamb and Complete Accessories	1	set			
4.7 Windows						
				1	lot	
4.7.1	W1 - Steel Louvered Window with Tubular Steel Framing	1	set			
4.7.2	W2- Steel Louvered Window with Tubular Steel Framing	1	set			
5 Plumbing Works						
5.1 Stormdrain, Downspout and Fittings						
				1	lot	
5.1.1	75 mm Ø S1000 PVC Pipe	4	pc			
5.1.2	75 mm Ø Elbow PVC	6	pc			
5.1.3	75 mm Ø Aluminum Downspout Strainer	2	set			
5.1.4	75 mm Ø HDPE Pipe for CisternWater Supply Line	130.00	m			
5.1.5	75 mm Ø Heavy Duty Brass Body Water Meter	1	pc			
5.1.4	75 mm Ø Heavy Duty Brass Body Gate Valve	2	pc			
5.1.5	75 mm Ø Heavy Duty Brass Body Check Valve	1	pc			
5.1.6	75 mm Ø Heavy Duty Brass Body Float Valve	1	pc			
5.1.9	Assorted Fittings and Accessories	1	lot			
6 Electrical Works						
6.1 Lighting, Power and Fire Pump System						
				1	lot	
6.1.1	36W Linear LED Pendant Light [Color: Daylight] Black Housing]	4	set			
6.1.2	12W Surface Mounted LED Panel Light [Color: Daylight]	5	set			
6.1.3	Universal Duplex Convenience Outlet	2	set			
6.1.4	2 Gang Switch Wide Series with LED	1	set			
6.1.5	2" x 4" GI Utility Box with Connector and Cover	2	set			
6.1.6	4" x 4" GI Junction Box with Connector and Cover	4	set			

6.1.7	Fire Pump Room Panel (Bolt-on) Main: 250AT 3P MCCB Branch: 1-450AT 3P MCCB, 1-60AT 3P MCCB, 1-30AT 3P MCCB, 2-20AT 2P MCCB Space: 0 With Busbars and Terminal Lugs Nema-1 Enclosure	1	set
6.1.8	12 inches x 12 inches x 4 inches (L x W x D) GA 16 Metal Pull box	5	set
6.1.9	3" Ø RSC	40	pc
6.1.10	1 1/2" Ø RSC	2	pc
6.1.11	3/4" Ø RSC	2	pc
6.1.12	1/2" Ø RSC	15	pc
6.1.13	1 1/2" Ø LFMC	8.00	m
6.1.14	3/4" Ø LFMC	10.00	m
6.1.15	1/2" Ø Mica Tube	10.00	m
6.1.16	100 mm ² Cu. THHN/THWN (STR)	375.00	m
6.1.17	30 mm ² Cu. THHN/THWN (STR)	50.00	m
6.1.18	5.5 mm ² Cu. THHN/THWN (STR)	25.00	m
6.1.19	3.5 mm ² Cu. THHN/THWN (STR)	1	box
6.1.20	10' Ground rod with solderless connector	1	lot
6.1.21	Conduit Support, Connector and Hanger (Elbow, Box Connector, Angle Bar, U-Bolt, Dynabolt with nut and washer)	1	lot
Total Bid Price			
		[In Words]	[In Figures]

[Signature]
[Name of Authorized Signatory]
[Position/Title]

[Handwritten signatures]